

Date: 2/18/13

PROPOSAL / CONTRACT

Worx Electrical Service, LLC.

2525 Marathon Lane Ft. Lauderdale, FL. 33312 Ph. 561-368-3131 / Fx: 954-584-2980

Proposal #: PF-769 .

"WORX ELECTRICAL SERVICE INC.", hereinafter referred to as "Electric Contractor", proposes to furnish material and labor in accordance with the job description identified in this Proposal/Contract pursuant to the following:

- SUBMITTED TO: Florida Atlantic University
- 2.CONTACT: Bob Thompson
- 3. CONTACT PHONES: (561) 297-2212 Fax: (561) 297-2260
- 4. Project Location / Name / P-#: Bldg. 80 Rm. 233 / Install Receptacle & Mount TV / P-
- 5. JOB DESCRIPTION:
- Install surface mounted hardwood back board on wall
 - Backboard shall be painted to match wall
 - Backboard shall be bolted to wall through wall studs
- Install owner supplied bracket & TV on new back board
- Install surface mounted wiremold track from TV straight down to 18" Aff.
- Install duplex receptacle behind TV
 - Receptacle shall be fed from existing local circuit

****Please see attached "Schedule A" ****

WE PROPOSE to perform the work as stated in this Contract in accordance with the specifications and plans submitted and completed in a workmanlike manner

for the sum of: Base Proposal \$ 745.22 .

Seven Hundred Forty Five Dollars and 22/100

with payments: standard AIA billing

This Contract is executed at "Ft. Lauderdale FLORIDA" by Electric Contractor

ACCEPTANCE OF PROPOSAL: The prices, specifications, terms and conditions are hereby accepted. You are authorized to do the work as specified. Payment will be made as outlined above. It is understood and agreed that this work is not provided for in any other agreement and no other contractual rights arise until this proposal is accepted in writing.

Worx Electrical Service, Inc.	Customer	
By: Chris Harker .	Ву:	-
Title: Estimator / Project Manager	Title:	
Date: 2/18/13	Date:	

^{***}Proposal is not inclusive of high and/or low voltage conduits and/or cabling

^{***}Proposal is inclusive of required permit, project release, inspections, as-built drawings, certificate of completion, certificate of contract performance forms.

SCHEDULE A

This schedule is attached to and made part of the above referenced Proposal/Contract number and is subject to the selling price, payment terms, scope of work and the Terms and Conditions set fourth herein

MATERIAL LIST

Proj. Name: Bldg. 80 Rm. 233 TV	Proj. #: P-
	109

DESCRIPTION	QTY	Cost	Total Cost
	4		\$6.88
wiremold	1	\$6.88	
1/2" EMT	20	\$0.24	\$4.80
1/2" EMT conn	2	\$0.24	\$0.48
1/2" EMT s/s coup	2	\$0.28	\$0.56
1/2" conduit hanger strap w/bolt	2	\$1.04	\$2.08
1/2" steel flex	6	\$0.74	\$4.44
1/2" squeeze flex strt conn malleable	2	\$1.70	\$3.40
cut-in Deep box	1	\$6.96	\$6.96
1900 Deep W/mud ring or blank	1	\$4.73	\$4.73
20A duplex receptacles TR	1	\$4.36	\$4.36
#12	50	\$0.15	\$7.50
Accessories	1	\$8.46	\$8.46
paint	1	\$31.25	\$31.25
Backboard	1	\$41.25	\$41.2
	TO	TAL COST	\$127.1

Proposal Breakout

	SUBTOTAL		\$599.00
*Permitting / Supervision	\$75.00	1	\$75.00
*Apprentice Labor	\$56.00	4	\$224.00
*Journeyman Labor	\$75.00	4	\$300.00

Materials Cost		\$127.15
Sub-Contractor /		\$0.00
	SUBTOTAL	\$127.15

	SUBTOTAL		\$19.07	C
Profit	(=9% x B)	9%	\$11.44	
Overhead	(=6% x B)	6%	\$7.63	

SUM TOTAL (= A + B + C)

\$745.22

^{* -} Labor rates are inclusive of labor burden, overhead, & profit